

March 20th, 2025

## Addendum 1

### Request for Tender Addendum 1 - 5330-02-1035 – Blueberry Pump Station S115

The Documents for this work are revised as noted herein. All such revisions become a part of the work and shall be included in your Tender. No consideration will be allowed for extras due to the tenderer not being familiar with this addendum.

#### REFERENCE: Questions/notes

#### QUESTION & ANSWER:

**1, Q.** Item 3.6 on Mini pile design, the contractor is responsible if the mini pile design fails or fails to meet intended.

**A.** If a pile fails testing, cost of replacement and testing shall be borne by the contractor.

**2, Q.** Is tree removal required on site.

**A.** Yes, please refer to the drawing plans and the Cascade Environmental Management Plan.

**3, Q.** Is there going to be details on how the gutters are to be affixed the roof/ installed.

**A.** The contractor is to propose attachment methodology to the existing roof to the Owner for review and approval.

**4, Q.** Is there going to be details on how the gutters are to be affixed the roof/ installed.

**A** We don't think shoring will be required, existing foundations will not be underpinned, and the works will be done when no snow will be on the roof, the existing foundations should be enough to carry the loads, it will be confirmed on site once exposed.

**5, Q.** DWG S010 What is the extent of the grade beam? It notes 350 x 450 deep however the linework is confusing.

**A** Please see attached re-issued for tender addendum S10 drawing including clarifications on extend of grade beams.

End of Addendum