

1.1 Owner: Resort Municipality of Whistler
(NAME OF OWNER)
Contract: RMOW 2025 Road and Trail Reconstruction
(TITLE OF CONTRACT)
Reference No. T00102
(OWNER'S CONTRACT REFERENCE NO.)

To All Tenderers: Date: April 14, 2025
This addendum shall form part of the original documents for the above noted contract and all other segments of the contract shall remain in force except as noted below:

1. – Form of Tender

DELETE: Form of Tender - Appendix 1 Page 4 to 7 of 14 inclusive
REPLACE WITH: Form of Tender - Appendix 1 Page 4 to 7 of 14 inclusive
Updated Form of Tender – Appendix 1 Page 4 to 7 of 14 inclusive (Addendum #2, Attachment #1)

All tenderers shall acknowledge receipt of Addendum #1 (One (1) page) and the following Attachments:

- Attachment #2 – Appendix 1 Page 4 to 7 of 14 inclusive

by signing in the space provided and submitting this signed addendum including attachments with the tender. Tenders submitted without acknowledgment of this addendum may be considered incomplete.

Receipt acknowledged and conditions agreed _____ day of _____, 2025

Tenderer

Signature

END ADDENDUM #2

SCHEDULE OF QUANTITIES AND PRICES - SUMMARY
(See paragraph 5.3.1 of the Instructions to Tender - Part II)

(All prices *Quotations* including the *Contract Price* shall include all *Taxes* , but shall not include *GST* . *GST* shall be shown separately.) 'S' Payment item in Supplementary Specifications

Item	Description	Amount
1.0	Lorimer Road - Balsam Way to Piccolo Road	
2.0	Blackcomb Way - Glacier Drive to Bridge	
3.0	Blackcomb Way Northbound (Between Sundial and Pan Pacific Roundabout)	
4.0	Blackcomb Way Northbound (Chateau to Bus Stop)	
5.0	Valley Trail - Alpha lake dog park to Lake Placid Rd - 450m	
6.0	Overexcavation (OPTIONAL)	
7.0	Hand Laid Asphalt MMCD Upper Course #2 (OPTIONAL)	

TENDER PRICE _____

GST(5%) _____

TENDER PRICE plus GST _____

Tenderer's Initials _____

1.0 Lorimer Road - Balsam Way to Piccolo Road

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 03 30 20 - CONCRETE WALKS, CURBS AND GUTTERS				
1.01	03 30 20 1.4.3	Concrete Rollover Curb	Linear Metre	8		
		MMCD 31 22 16 - RESHAPING GRANULAR ROADBED				
1.02	31 22 16S 1.4.1S	Reshaping	Square Metre	4600		
		MMCD 31 24 13 - ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
1.03	31 24 13 1.10.10	Over Excavation 0.3m Depth c/w Offsite Disposal, Backfilling and Compaction (Optional)	Cubic Metre	30		
		MMCD 32 11 23 - GRANULAR BASE				
1.04	32 11 23 1.4.1	19mm minus Granular Base - variable thickness includes placement, grading and compaction (Optional)	Tonne	760		
1.05	32 11 23 1.4.1	Granular Shouldering - 1.0m wide, variable thickness includes placement, grading and compaction (Optional)	Lin. M.	1000		
		MMCD 32 01 16.7 - COLD MILLING				
1.06	32 01 16.7S 1.5.1S 1.5.1.3S	Full Depth Milling	Square Metre	4600		
		MMCD 32 12 13.1 - ASPHALT TACK COAT				
1.07	32 12 13.1 1.5.1	Asphalt Tack Coat	Square Metre	4600		
		MMCD 32 12 16 - HOT-MIX ASPHALT CONCRETE PAVING				
1.08	32 12 16 1.5.1	Remove and Replace 80mm Raised Asphalt Crosswalk as per RMOW Standard detail R3	Lump Sum	2		
1.09	32 12 16 1.5.1	Machine Laid MMCD Lower Course #1 - 50 mm	Tonne	570		
1.10	32 12 16 1.5.1	Machine Laid MMCD Upper Course #1 - 50 mm	Tonne	570		
Note:		Including 2 x speed bumps and swale/scupper				

2.0 Blackcomb Way - Glacier Drive to Bridge

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 31 22 16 - RESHAPING GRANULAR ROADBED				
2.01	31 22 16S 1.4.1S	Reshaping	Square Metre	1100		
		MMCD 32 11 23 - GRANULAR BASE				
2.02	32 11 23 1.4.1	19mm minus Granular Base - variable thickness includes placement, grading and compaction (Optional)	Tonne	165		
		MMCD 32 01 16.7 - COLD MILLING				
2.03	32 01 16.7S 1.5.1S 1.5.1.3S	Full Depth Milling	Square Metre	1100		
		MMCD 32 12 13.1 - ASPHALT TACK COAT				
2.04	32 12 13.1 1.5.1	Asphalt Tack Coat	Square Metre	1100		
		MMCD 32 12 16 - HOT-MIX ASPHALT CONCRETE PAVING				
2.05	32 12 16 1.5.1	Machine Laid MMCD Lower Course #1 - 50 mm	Tonne	140		
2.06	32 12 16 1.5.1	Machine Laid MMCD Upper Course #1 - 50 mm	Tonne	140		
Note:						

3.0 Blackcomb Way Northbound (Between Sundial and Pan Pacific Roundabout)

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 32 01 16.7 – COLD MILLING				
3.01	32 01 16.7S 1.5.1S 1.5.1.3S	Milling 50mm Thickness	Square Metre	130		
		MMCD 32 12 13.1 – ASPHALT TACK COAT				
3.02	32 12 13.1 1.5.1	Asphalt Tack Coat	Square Metre	130		
		MMCD 32 12 16 – HOT-MIX ASPHALT CONCRETE PAVING				
3.03	32 12 16 1.5.1	Machine Laid MMCD Upper Course #1 - 50 mm	Tonne	20		
Note:						

4.0 Blackcomb Way Northbound (Chateau to Bus Stop)

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 32 01 16.7 – COLD MILLING				
4.01	32 01 16.7S 1.5.1S 1.5.1.3S	Milling 50mm Thickness	Square Metre	555		
		MMCD 32 12 13.1 – ASPHALT TACK COAT				
4.02	32 12 13.1 1.5.1	Asphalt Tack Coat	Square Metre	555		
		MMCD 32 12 16 – HOT-MIX ASPHALT CONCRETE PAVING				
4.03	32 12 16 1.5.1	Machine Laid MMCD Upper Course #1 - 50 mm	Tonne	70		
Note:						

5.0 Valley Trail - Alpha lake dog park to Lake Placid Rd - 450m

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 31 22 16 - RESHAPING GRANULAR ROADBED				
5.01	31 22 16S 1.4.1S	Reshaping	Square Metre	1380		
		MMCD 31 24 13 - ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
5.02	31 24 13 1.8.5.6S	Asphalt Removal (up to 100mm asphalt thickness)	Square Metre	1380		
		MMCD 32 11 23 – GRANULAR BASE				
5.03	32 11 23 1.4.1	19mm minus Granular Base - variable thickness includes placement, grading and compaction	Tonne	80		
5.04	32 11 23S 1.4.5S	19mm minus crushed granite shouldering - 0.6m width x 75mm thickness includes placement, grading and compaction	Tonne	95		
		MMCD 32 12 16 – HOT-MIX ASPHALT CONCRETE PAVING				
5.05	32 12 16 1.5.1	Machine Laid MMCD Upper Course #1 - 75mm	Tonne	260		
Note:						

Optional Items

6.0 Overexcavation (OPTIONAL)

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 31 24 13 - ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
6.01	31 24 13S 1.8.14S	Overexcavation "unsuitable material", Off Site Disposal c/w crushed granular base backfill	Cubic Metre	100		

7.0 Hand Laid Asphalt MMCD Upper Course #2 (OPTIONAL)

ITEM NO.	MMCD REF.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
		MMCD 32 12 16 - HOT-MIX ASPHALT CONCRETE PAVING				
7.01	32 12 16 1.5.1	Single Lift, 75mm thickness up to 1,000m ²	Tonne	100		
7.02	32 12 16 1.5.1	Single Lift, 75mm thickness over 1,000m ²	Tonne	100		

Tenderer's Initials _____